

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

AUG 31 1964

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Fred B. Anschutz

Complete Address: 1521 Wichita Plaza, Wichita, Kansas

Lease Name Carroll Well No. # 1

Location C SW SE Sec. 2 Twp. 35 Rge. 9 (E) (W) W

County Harper Total Depth 5423

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Terrel Drilling & Producing

Address: Box 606, Russell, Kansas License No.     

Operation Completed: Hour 11:00PM Day 28th Month August Year 1964

The Above well was plugged as follows:

208' of 8 5/8" surface pipe, cemented with 220 sacks, circulated. Hole  
was filled with drilling mud to 200', 1st cementing plug, bridged solid  
with hulls, on fluid at 200', and cemented with 25 sacks. Hole was fill-  
ed with drilling mud to 40', 2nd cementing plug, bridged solid with hulls,  
on fluid at 40', and cemented with 10 sacks to the base of the cellar.  
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 9/1/64  
INV. NO. 9941-W