

KANSAS

14

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
APR 6 1970
CONSERVATION DIVISION
Wichita, Kansas
04-06-70

Operator's Full Name Spector Pipe & Supply, Inc.

Complete Address Box 169 Russell, Kansas 67665

Lease Name E. E. Jensen Well No. 2

Location SE SW NW Sec. 34 Twp. 11 Rge. (E) (W) 19W

County Ellis Total Depth 3584

Abandoned Oil Well XXX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Lynch Casing Pulling Co.

Address Great Bend, Kansas 67530 License No. 457

Operation Completed: Hour 3P Day 4 Month 4 Year 1970

The above well was plugged as follows:

Total Depth 3584' 8 5/8 csg set at 1372' cwc 500 sk.

5 1/2 csg set at 3567' cw 125 sk cmt.

Filled 5 1/2 csg W/sd (3550-3584) Dumped 5 sk cmt W/dump bailer. (3510-3550)

Cutoff and recovered 2616' of 5 1/2 csg.

Mud no 550' sset rock bridge (540-550)

Filled to surface W/7 yds readymix cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 4/6/70
INV. NO. 1681-4