

15-051-02341-0001

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 6 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Spector Pipe & Supply, Inc.

Complete Address Box 169 Russell, Kansas 67665

Lease Name E. E. Jensen Well No. 3

Location NW SW NW Sec. 34 Twp. 11 Rge. (E) (W) 19

County Ellis Total Depth 3740'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Lynch Casing Pulling Co.

Address Great Bend, Kansas License No. 457

Operation Completed: Hour 11.30A Day 4 Month 4 Year 1970

The above well was plugged as follows:

Total Depth 3740' 8 5/8 csg set at 1428' cwc

5 1/2 csg set at 3635' cw 150 sk cmt.

Filled 5 1/2 csg W/sd (3620-3740) Dumped 5 sk cmt W/dump bailer. (3580-3620)

Cutoff and recovered 2915' of 5 1/2 csg.

Mud to 650' Set wood plug, rock & sand (635-650) Dumped 3 yds readymix (435-635)

Mud to 215' Set wood plug, rock and sand (200-215) Dumped 3 yds readymix (0-200)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ren J. Massey
Well Plugging Supervisor

DATE 4/6/70
INV. NO. 1682-4