

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
APR 6 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Spector Pipe & Supply, Inc.

Complete Address Box 169 Russell, Kansas 67665

Lease Name Jensen Well No. 4

Location SW NW NW Sec. 34 Twp. 11 Rge. (E) (W) 19

County Ellis Total Depth 3633

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Lynch Casing Pulling Co.

Address Great Bend, Kansas License No. 457

Operation Completed: Hour 11A Day 4 Month 4 Year 1970

The above well was plugged as follows:

Total Depth 3633' 8 5/8 csg set at 1420' cwc 500 sk.

5 1/2 csg set at 3630' cw 700 sk cmt.

Filled 5 1/2 csg W/sd (3620-3633) Dumped 5 sk cmt W/dump bailer. (3580-3620)

Cutoff and recovered 1777' of 5 1/2 csg.

Mud to 650' set rock bridge (640-650) Dumped 3 yds readymix cmt (440-640)

Mud to 215' set rock & sand (200-215) Dumped 3 yds readymix cmt (0-200)

I hereby certify that the above well was plugged as herein stated.

Signed: Don L. Mansel
Well Plugging Supervisor

INVOICED

DATE 4/6/70
INV. NO. 1683-U