

15-051-20341-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
NOV 12 1968
CONSERVATION DIVISION
Wichita, Kansas
11-12-1968

Operator's Full Name Thunderbird Drlg., Inc.

Complete Address: 400 N. Woodlawn Suite 7 Wichita, Kansas

Lease Name Weigle "A" Well No. 1

Location S/2 S/2 NE/4 Sec. 8 Twp. 13 Rge. 16 (E) (W) XX

County Ellis Total Depth 3517

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: Sage drlg.

Address: Wichita, Kansas License No.

Operation Completed: Hour 4:30 P Day 8 Month 11 Year 1968

The Above well was plugged as follows:

RTD 3517# 8 5/8 csg set at 230' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunne d pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sc cmt.

thru drill pipe. Heavy mud to 215' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey
Well Plugging Supervisor

INVOICED

DATE 11/12/68

INV. NO. 8807-W