

15-051-30382-00-00

Form CP-3
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
NOV 14 1966
CONSERVATION DIVISION
STATE CORPORATION COMMISSION

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Woodman-Iannitti Drilling Company

Complete Address: 706 Union National Bldg., Wichita, Kansas

Lease Name Dinkel Well No. 1

Location SW SW SE Sec. 8 Twp. 13 Rge. 16 (E) (W) X

County Ellis Total Depth 3460* 3560 B.O.B. K.C.

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 5:30 A Day 11 Month 11 Year 1966

The Above well was plugged as follows:

RTD3460" 8 5/8 csg set at 163' cwc 125 sc.

Gunned pits, circulated heavy mud, set cementing plug at 550' and displaced 25 sc

cement thru drill pipe. Heavy mud to 155' set cementing plug and displaced 20 sc

cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/4 sc hulls and 15

sc cement to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/15/66

INV. NO. 4288-W

Signed: Leo Massey
Well Plugging Supervisor