

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-051-20365-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name V. Francis Weigel

Complete Address P.O. Box 244, Gorham Ks. 67640

Lease Name Schmeidler A

Well No. 1

Location NV NE NW

Sec. 11 Twp. 13 Rge. 16 (East) West

County Ellis

Total Depth 3510'

Abandoned Oil Well XXX Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase, Ks. 67524

License No.

Operation Completed: Hour: 3:00 PM Day: 19 Month: Feb. Year: 19 82

Plugging Operations attended by Agent?: All XXX Part None

The above well was plugged as follows:

8 5/8" - 151' S.P. cuc. W/ 100 sacks common. 4 1/2" casing set at 3509' W/ 200
sacks common. Plugged back to 3481'. Top perf. at 3159'. Pushed plug to 3100'
W/ sand & 4 sacks cement on top. Shot pipe 3 times and recovered 1139'.

Ordered 140 sacks 50/50 posmix 4% Gel.- 3% CA1.Cl., 5 sacks of hulls, 19 sacks
of Gel. and 8 5/8" plug. Pumped in to 8 5/8" S.P. W/ pump truck, 4 sacks of hulls
15 sacks of Gel., 70 sacks of cement, 4 sacks of Gel., 1 sack of hulls, released
plug and followed W/ 70 sacks cement. Maximum Pressure 200 pounds.

Amount of Surface Casing: 151' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed:
Conservation Division Agent

INVOICED

TEL. 2-2282

NO. 9461-W

STATE CORPORATION COMMISSION
RECEIVED
FEE
06-28-82
CONSERVATION DIVISION
Wichita, Kansas