

15-051-20284-00-00

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202RECEIVED
STATE CORPORATION COMMISSION
JUL 29 1968
CONSERVATION DIVISION
Wichita, Kansas
07-29-1968Operator's Full Name W. Francis WeigelComplete Address: Box 244 Victoria, KansasLease Name Reidel Well No. 1Location SW SE SW Sec. 11 Twp. 13 Rge. 16 (E) X (W) XCounty Ellis Total Depth 3440'Abandoned Oil Well Gas Well Input Well SWD Well D & A XOther well as hereafter indicated: Plugging Contractor: L. J. DreilingAddress: Victoria, Kansas License No. Operation Completed: Hour 7 P Day 26 Month 7 Year 1968

The Above well was plugged as follows:

RTD 3440' 8 5/8 csg set at 158' cwc. Cem. Mat. 100 sc 50-50 poz cem. W/6% total gel.
at 500'

Gunned pits, circulated heavy mud, set cementing plug and displaced 70 sc cem.

thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

7/29/68

INV. NO.

8194-W

Signed: Geo F. Massey

Well Plugging Supervisor