

15-051-00332-00-01

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

DEC 26 1972  
12-26-1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name R. P. Nixon

Complete Address Box 589 Russell, Kansas 67665

Lease Name Dortland Well No. 1

Location NE SW NW Sec. 13 Twp. 13 Rge. (E) (W) 16

County Ellis Total Depth 3390'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Co. Tools by Allied Cementing Co.

Address        License No.       

Operation Completed: Hour 2:30 P Day 22 Month 12 Year 1972

The above well was plugged as follows:

Total Depth 3390' 8 5/8 csg set at 243' cwc

5 1/2 csg set at 3386' cw 100 sk cmt.

5 1/2 csg PBSD 3230' with top perf. (3195-3199)

No pipe recovered.

Pumped down 5 1/2 csg with 200 lbs hulls, 33 sk gel & water, released 5 1/2 plug and

pumped 300 lbs hulls and 50 sk cmt with 250 lbs. PP.

Pumped down annulus with 75 sk cmt W/100 lbs hulls. SI pres. 1000 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: R. P. Nixon  
Well Plugging Supervisor

INVOICED

DATE 12/26/72

INV. NO. 6770-W