

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-051-22573-00-00

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Aylward Drilling Company

Complete Address 909 First National Bank Bldg., Wichita, Kansas 67202

Lease Name Dortland Well No. #1

Location SW/2-NW Sec. 13 Twp. 13 Rge. 16 (East) (West)

County Ellis Total Depth 3410'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Rains & Williamson Oil Co., Inc.

Address 435 Page Court, 220 W. Douglas, License No.
Wichita, Kansas 67202

Operation Completed: Hour: 2:00AM. Day: 12th Month: Oct. Year: 1981

Plugging Operations attended by Agent? All Part None XX

The above well was plugged as follows:

8 5/8"-238' sp. cuc. w/150 sacks common-2% Gel.-3% Cal. Cl.

Ordered 125 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spotted with drill stem with heavy mud between all plugs.

1st plug @ 680' w/70 sacks cement

2nd plug @ 220' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40 ft. w/10 sacks cement

5 sacks of cement in rat hole.

STATE CORPORATION COMMISSION

10-19-1981

CONSERVATION DIVISION

Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: J. P. Schmidt

Conservation Division Agent
& Marian Schmidt

DATE 11-19-81

REV. NO. 8297-W