



15-167-21320-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Rec'd
07-01-82

Dear Sir:

Mr. Bill Kelso of Kelso Casing Pulling has this date requested permission to plug the following described well:

Operator's Full Name: Petro-Lewis Corporation

Complete Address: 3100 N. Main, Great Bend, Ks. 67530

Lease Name: Strecker Well No. 1

Location: SW SW NE Sec. 25 Twp. 13 Rge. 15 (E) (W)

County: Russell Total Depth: 3354'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Kelso was instructed to plug the well as follows:

8 5/8"-958' S.P. cuc. w/ common cement. 5 1/2" set at 3354' w/100 sacks common cement. Plug back T.D. 3340'. Top perf. 3322'. Plugged bottom w/ sand & 5 sacks cement. to 3260'. Shot pipe 5 times & recoverd 2320'. Ordered 140 sacks 50/50 posmix-4% Gel.-3% Cal.Cl., 15 sacks Gel., 4 sacks, Hulls & 8 5/8" plug.
Pumped into S.P. w/pump truck, 3 sacks hulls, 12 sacks Gel., 70 sacks cement 3 sacks Gel., 1 sack hulls, released plug & followed w/70 sacks cement.

Maximum pressure 600 pounds

Very truly yours,


Conservation Division Agent