

State of Kansas



FORM - CP-2  
Rev. 6-26-62

15-077-00281-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 31 1964

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Bill Roof of Terrel Drilling & Producing has this date requested permission to plug the following described well:

Mr. Roof guarantees payment of the plugging fee.

Operator's full Name: Fred B. Anschutz

Complete Address: 1521 Wichita Plaza, Wichita, Kansas

Lease Name: Carroll Well No. # 1

Location: C SW SE Sec. 2 Twp. 35 Rge. 9 (E) (W) W

County Harper Total Depth 5423 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Roof was instructed to plug the well as follows:

208' of 8 5/8" surface pipe, cement circulated with 220 sacks.  
Fill hole with drilling mud to 200', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drilling  
mud to 40', 2nd cementing plug, bridge with hulls, and cement  
with 10 sacks to base cellar. Bridge and cement rat hole with  
2 sacks.

Very truly yours,

*Archie Elving*