

15-167-03812-00-00

State of Kansas



FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 5 1964
02-05-1964
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Sam Farmer of John O. Farmer, Inc. has this

date requested permission to plug the following described well:

Mr. John O. Farmer guarantees payment of the plugging fee.

Operator's full Name: Nadel & Gussman & John O. Farmer, Inc.

Complete Address: Box 352, Russell, Kansas

Lease Name: Novak Well No. 1

Location: SW NW SW Sec. 30 Twp. 13 Rge. 15 (E) (W) W

County Russell Total Depth 3430 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sam Farmer was instructed to plug the well as follows:

8 5/8" 154' Cwc.

Filled hole with heavy mud to 300'; set plug; displaced
20 sax cement thru drill pipe. Mud to 150'; set plug with
1/4 sax hulls; displaced 20 sax cement thru drill pipe. Mud
to 40'; 1/2 sax hulls; plug & displaced 10 sax cement,
cementing to base of cellar.

Very truly yours,

Don Truman
Well Plugging Supervisor