

State of Kansas



15-051-22717-00-00
FORM CP-2

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water

WICHITA, KANSAS 67202

December 11, 1981

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Fred Cameron of Big Springs Drilling, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Martin Oil Producers, Inc.

Complete Address: 1010 Union Center, Wichita, Kansas 67202

Lease Name: Brungard T Well No. 1

Location: SW NW NE ~~5 13S 7E~~ Sec. 5 Twp. 13S Rge. 16W (W)

County: Ellis Total Depth: 3530'

Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☒

Other well as hereafter indicated: _____

Mr. Cameron was instructed to plug the well as follows:

8 7/8" - 248' - 200 sacks Dakota 716-816 Circulate hole and Fill with mud. Pump 70 sacks cement through drill pipe at 900'. Pump 50 sacks cement through drill pipe at 300'. Fill hole with mud to 40' Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement. Cement rat hole with 10 sacks cement.

Very truly yours,

RECEIVED
STATE CORPORATION COMMISSION

Anthony J. Lomax
Conservation Division Agent

DEC 16 1981
12-16-1981
CONSERVATION DIVISION
Wichita, Kansas