



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 12 1968
 CONSERVATION DIVISION
 Wichita, Kansas

11-12-1968

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Galloway of Sage Drlg.Co. Inc. has this
 date requested permission to plug the following described well:

Mr. Galloway guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drlg., Inc.

Complete Address: 400 N. Woodlawn Suite 7 Wichita, Ks.

Lease Name: Weigle "A" Well No. 1

Location: S/2 S/2 NE/4 Sec. 8 Twp. 13 Rge. 16 (E)(W) X

County: Ellis Total Depth 3517 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Galloway was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600' and displace
70 sc cement thru drill pipe. Heavy mud to 215' set cementing plug and
displace 20 sc cement to Heavy mud to 40' set cementing plug, 1/2 sc hulls
and 10 sc cement to base of cellar. Plug rat hole with 2 sc cement.

Very truly yours,

Leo F. Murray
 Conservation Division Agent