

State of Kansas



FORM CP-2

15-D51-22573-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Bob Delaney of Rains & Williamson Oil Co., Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Aylward Drilling Company

Complete Address: 909 First Nat'l Bank Bldg., Wichita, Ks. 67202

Lease Name: Dortland Well No. #1

Location: SW/2-NW Sec. 13 Twp. 13 Rge. 16 (E) (W)

County: Ellis Total Depth: 3410'

Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☒

Other well as hereafter indicated:

Mr. Bob Delaney was instructed to plug the well as follows:

8 5/8"-238' sp. cuc. w/150 sacks common-2% Gel.-3% Cal. Cl.

Ordered 125 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spotted with drill stem with heavy mud between all plugs.

1st plug @ 680' w/70 sacks cement

2nd plug @ 220' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40 ft. w/10 sacks cement

5 sacks of cement in rat hole.

Very truly yours,

RECEIVED
10-19-1981
CONSERVATION DIVISION
Wichita, Kansas

Phillip R. Dick
Conservation Division Agent