

6 070818

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 051-24,631-00-00  
SW NE SW 11, T 13 S, R 17 W/EX  
1650 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5140  
Operator: Frontier Oil Company  
Name & Address: 125 N. Market Suite 1720  
Wichita, Ks. 67202  
George A. Angle

Lease Name Dreiling Well # 1  
County Ellis 116.68  
Well Total Depth 3590 feet  
Conductor Pipe: Size 0 feet  
Surface Casing: Size 8 5/8 feet 232

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Red Tiger Drilling License Number \_\_\_\_\_ Tag 82  
Address 125 n. Market Suite 1720 Wichita, Ks. 67202

Company to plug at: Hour: AM Day: 21 Month: Dec Year: 19 89

Plugging proposal received from Ken Lyle  
(company name) Red Tiger Drilling (phone) \_\_\_\_\_

were: 8 5/8" 232' s.p. cwc w/140 sks 60/40 poz 2% gel 3% cc. By Allied Cement.  
Arb. 3562'. Elv. 2030' Any 1202' No circulation problems. Mud condition 47 vis.  
9.8 weight 0.8 water loss. Proposal 215 sks 60/40 poz 6% gel 3% cal cl w/1 sk f.c. and  
8 5/8" plug. Spot with drill stem, circulate, heavy mud between all plugs. 25 sks at  
3540' w/25 sks - 25 sks at 1220' - 100 sks w/1 sk f.c. at 650' 40 sks at 280' wiper plug  
10 sks at 40' . 15 sks rathole (cir)

Plugging Proposal Received by *MJS* Marion J. Schmidt  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 3:00PM Day: 21 Month: Dec Year: 19 89  
Frontier ordered 215 sks 60/40 poz 6% gel 3% cal al and

ACTUAL PLUGGING REPORT  
8 5/8" plug. Spotted with drill stem, circulated, heavy mud between all plugs. 1st plug  
at 3540' w/25 sks cement. 2nd plug at 1220' w/25 sks cement. 3rd plug at 650' w/100 sks  
cement w/1 sk f.c. 4th plug at 280' w/40 sks cement. 5th plug wiper plug at 40 w/10 sks  
cement. 15 sks in rathole (cir) by Allied.

STATE CORPORATION COMMISSION

JAN 17 1990

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of Kansas form.)

part did not observe this plugging.

INVOICED  
JAN 24 1990

Signed *Marion J. Schmidt*  
(TECHNICIAN)  
Marion J. Schmidt

DATE \_\_\_\_\_  
INV. NO. 27123