

153.73

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-21267-00-00
Spot: NWSENWSW Sec/Twnshp/Rge: 31-10S-30W
1786 feet from S Section Line, 922 feet from W Section Line
Lease Name: BECKMAN Well #: 1
County: SHERIDAN Total Vertical Depth: 4730 feet

Operator License No.: 33186
Op Name: LB EXPLORATION, INC.
Address: 2135 2ND RD
HOLYROOD, KS 67450

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	282		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/11/2010 7:00 AM
Plug Co. License No.: 33493 Plug Co. Name: AMERICAN EAGLE DRILLING LLC
Proposal Rcvd. from: TODD Company: LB EXPLORATION, INC. Phone: (785) 252-8034

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER WitnessType: NONE
Date/Time Plugging Completed: 10/11/2010 8:15 AM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

1st. Plug at 2540' w/25 sxs.
2nd. Plug at 1650' w/100 sxs.
3rd. Plug at 330' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.

Perfs:

12/10/10
201060138

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

RECEIVED
OCT 18 2010
KCC WICHITA

District: 04

Signed Ed Schumacher
(TECHNICIAN) CM

OCT 14 2010