


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Barber County. Sec. 30 Twp. 31S Rge. 10 (X) (W)
Location as "NE/CNW/SW" or footage from lines NW NW NW
Lease Owner Trans Era Petroleum, Inc.
Lease Name McReynolds Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4/28/55 19
Application for plugging filed 8/4/55 19
Application for plugging approved 8/4/55 19
Plugging commenced 8/21/55 19
Plugging completed 8/21/55 19
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Merle Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4985 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	295	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

Plugged back with crushed rock from 4560' to 4490'. Dumped 5 sac cement with dump bailer at 4490', top of cement, 4460'. Filled with mud to 275', set rock bridge, dumped 20 sac cement. Top of cement, 210'. Filled with mud to 35', set rock bridge, dumped 10 sac cement for cap.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J & M Casing Pulling Company
Address Box 711 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Robert B. Snyder (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert B. Snyder
(Address) _____

Subscribed and Sworn to before me this 29th day of August, 19 55
My commission expires 1-30-57



Margie Cooper Notary Public.

PLUGGING
FILE SEC 30 T 31 R 10W
BOOK PAGE 40 LINE 19

RECEIVED
STATE CORPORATION COMMISSION
AUG 31 1955
CONSERVATION DIVISION
Wichita, Kansas

Trans Era Petroleum, Inc.
McReynolds #1

NW NW NW 30-31-10
Barber County, Kansas

Total Depth: 4985

Comm: /4/2/55
Comp: 4/28/55

Casing:
8 5/8" @ 295
5 1/2" @ 4984

Cement
200 sacks of Monarch
200 sacks of Monarch

FORMATION	DEPTH
Sand	50
Sand & Redbed	150
Red rock	230
Red Bed	295
Redbed & Shale	850
Shale	1200
Shale & salt	1310
Shale & shells	1385
Lime & shale	1415
Shale & lime	1745
Lime & shale	2000
Lime	2070
Lime & shale	3727
Lime	3783
Lime & shale	3886
Lime	4231
Lime & shale	4494
Mississippi	4520
Mississippi Chet & Chert	4559
Chet & Shale	4580
Lime & Chert	4603
Chert & Shale	4619
Lime & Shale	4644
Shale	4664
Shale & lime	4686
Shale	4741
Viola	4755
Shale & Lime	4791
Viola	4806
Simpson	4810
Shale & sand	4827
Shale	4833
Sand	4882
Sand & shale	4956
Shale	4962
Arbuckle lime	4985

STATE OF KANSAS)
) ss:
RUSSELL COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

Robert B. Snyder

Subscribed and sworn to before me this 5th day of May, 1955.

Margie Cooper
Notary Public



My commission expires: 1-30-57

PLUGGING
FILE SEC 30 T 31 R 10 W
BOOK PAGE 140 LINE 19

1955
COMMISSION
CONSOLIDATION DIVISION
Wichita, Kansas