

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

Rec. 09-25-1985

API NUMBER 15-167-22,657-00-00

LEASE NAME Dorthea Dumler

WELL NUMBER 3

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

4950 Ft. from S Section Line

660 Ft. from E Section Line

LEASE OPERATOR H & H Production, Inc.

SEC. 27 TWP. 13 RGE. 15 ~~OR~~ (W)

ADDRESS Box 348 Russell, KS 67556

COUNTY Russell

PHONE#(913) 483-4898 OPERATORS LICENSE NO. 7124

Date Well Completed 9-18-85

Character of Well \_\_\_\_\_

Plugging Commenced 9-19-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9-19-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays, Ks.  
to be filed by \_\_\_\_\_

Is ACO-1 filed? operator If not, is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 3347

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Bottom Plug: @ 3335' w/20 sacks cement thru drill pipe

Next Plug: @ 960' w/ 20 " " " " "

Next Plug: @ 525' w/100 " " " " "

Top Plug: @ 40' w/1 sack Hulls & 10 sacks cement 10 sacks cement in Rat Hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson (Employee of Operator) or ~~(Operator)~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leonard Williamson

(Address) Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 24 day of Sept., 19 85

Dorothy M. Hague  
Notary Public

My Commission Expires: 4-29-86



DRILLER'S WELL LOG

DATE COMMENCED: September 13, 1985  
 DATE COMPLETED: September 18, 1985

H & H Production, Inc.  
 DORITHEA DUMLER #3  
 N/2 NE NE  
 Sec. 27, T13S, R15W  
 Russell County, Ks.

ELEVATION: 1902 K.B.

0 - 260' Surface Soil, Clay, Rock, Sand  
 260 - 956' Shale, Red Bed  
 956 - 999' Anhydrite  
 999 - 2754' Lime & Shale  
 2754 - 2780' Lime  
 2780 - 2791' Shale & Sand  
 2791 - 3017' Lime  
 3017 - 3021' Shale  
 3021 - 3070' Lime & Shale  
 3070 - 3316' Lime  
 3316 - 3331' Shale & Lime  
 3331 - 3347' Dolomite  
 3347' RTD

FORMATION DATA

Anhydrite	956'
Howard	2754'
Severy	2780'
Topeka	2791'
Heebner	3017'
Toronto	3038'
Douglas	3050'
Kansas City	3070'
Base K.C.	3316'
Arbuckle	3331'
RTD	3347'

Surface Pipe: Set new  
 8-5/8", 23# pipe @474'  
 w/200 sacks 60/40 pozmix  
 2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS  
 COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

*Leonard Williamson*

scribed and sworn to before me this 24 day of September 1985.

mm, Expires:

*Dorothy M Hague*  
 Notary Public

1-86

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 25 1985  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 09-25-1985