

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-167-22,687-00-00

LEASE NAME Edna Scott

WELL NUMBER 1

330 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 28 TWP. 13 RGE. 15 (X) or (W)

COUNTY Russell

Date Well Completed 4-6-86

Plugging Commenced 4-6-86

Plugging Completed 4-7-86

LEASE OPERATOR H & H Production, Inc.

ADDRESS P.O. Box 348 Russell, KS 67556

PHONE#(913) 483-4898 OPERATORS LICENSE NO. 7124

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays, Ks.  
to be filed by

Is ACO-1 filed? operator If not, is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Bottom Plug: @ 3360' w/20 sacks cement thru drill pipe

Next Plug: @ 970' w/20 " " " " " "

Next Plug: @ 500' w/100 " " " " " "

Top Plug: @ 40' w/1 sacks Hulls & 10 sacks cement 15 sacks in Rat Hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson

(Employee of Operator) or ~~XXXXXX~~ of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leonard Williamson

(Address) Box 823 Great Bend, KS 67530

DESCRIBED AND SWORN TO before me this 9<sup>th</sup> day of April, 1986

Dorothy M. Dague  
Notary Public

Commission Expires: 4-29-86



DRILLER'S WELL LOG

DATE COMMENCED: April 1, 1986  
DATE COMPLETED: April 6, 1986

H & H Proudtion, Inc.  
EDNA SCOTT #1  
SW SE SW  
Sec. 28, T13S, R15W  
Russell County, Ks.

ELEVATION: 1922 K.B.

0 - 968' Surface Soil, Shale, Sand, Red Bed  
968 - 1012' Anhydrite  
1012 - 2806' Lime & Shale  
2806 - 3032' Lime  
3032 - 3036' Shale  
3036 - 3054' Lime & Shale  
3054 - 3068' Lime  
3068 - 3079' Shale  
3079 - 3320' Lime  
3320 - 3358' Shale, Lime, Chert, Sand  
3358 - 3400' Dolomite  
3400' RTD

FORMATION DATA

Anhydrite 968'  
Topeka 2806'  
Heebner 3032'  
Toronto 3054'  
Douglas 3068'  
Kansas City 3079'  
Base K.C. 3320'  
Conglomerate 3336'  
Arbuckle 3358'  
RTD 3400'

Surface Pipe: Set new  
8-5/8", 20# pipe @450'  
w/200 sacks 60/40 pozmix  
2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS  
COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 9<sup>th</sup> day of April 1986.

My Comm. Expires:

4-29-88

Dorothy M. Haque  
Notary Public

STATE CORPORATION COMMISSION  
APR 10 1986  
0410-1986  
CONSERVATION DIVISION  
Wichita, Kansas

