

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-167-19000-00-00

LEASE NAME DUMLER "L"

WELL NUMBER 1

330 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 28 TWP. 13 RGE. 15W (E) or (W)

COUNTY Russell

Date Well Completed _____

Plugging Commenced 4-5-01

Plugging Completed 4-6-01

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR NEW GENERATION OIL, INC.

ADDRESS 2015 E. Hwy. 40 Russell, Kansas 67665

PHONE(S) (785) 483-8515 OPERATORS LICENSE NO. 31418

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Jay Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

APR 19 2001

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 261' | None |
| | | | | 5-1/2" | 3379' | 2213' |
| | | | | | | |
| | | | | | | |

04-19-2001
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging materials were used, state the character of same and depth placed, from _____ feet to _____ feet each section.

Plugged off bottom with sand to 2750' and 5 sks. cement. Shot pipe @2213', pipe was eaten into @500', ran in 1800' of 2-3/8" tubing, pumped 150 sks. cement w/400# hulls, pulled tubing to 950', pumped 50 sks. cement and 100# hulls, pulled up to 260', circulated 50 sks. cement to surface. 60/40 pos, 10% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: New Generation Oil, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 17th day of April, XX 2001

[Signature]
Notary Public

My Commission Expires: _____



Form CR
Revised 05-

OR