

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-24,9080000

LEASE NAME LaMac Trust

WELL NUMBER 1

4,950 Ft. from S Section Line

1,650 Ft. from E Section Line

SEC. 5 TWP. 13 RGE. 16 (E) or (W)

COUNTY Ellis

Date Well Completed 11-16-95

Plugging Commenced 11-16-95

Plugging Completed 11-17-95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR R.P. Nixon Operations, Inc.

ADDRESS 207 W. 12th, Hays, Kansas 67601

PHONE#(913) 628-3834 OPERATORS LICENSE NO. 5252

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-16-95 (date)

by Bruce Bayse (KCC District Agent's Name).

Is ACO-1 filled? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3,505'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|------------------|
| | | | | 8 5/8" | 210' | Cmt'd. w/135 sax |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Push bridge plug to 1,170', pump 25 sax cement down drill pipe. Push bridge plug to 600'. Pump 100 sax cement down drill pipe. Push bridge plug to 260', pump 40 sax cement down drill pipe. Push wiper plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole. Plug down at 6:15 AM.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co.

Address Shields Bldg., Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R.P. Nixon Operations, Inc.

STATE OF KANSAS COUNTY OF RUSSELL

Jack P. Beeman, Sec.-Treas. (Employee of Shields Drilling Co. or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 27th day of November, 19 95

My Commission Expires:



Notary Public




15-051-24908-00-00
Shields

Russell, Kansas

WELL LOG

Operator: R.P. Nixon Operations, Inc.
Well: LaMac Trust #1
Commenced: November 10, 1995
Completed: November 17, 1995
Contractor: Shields Drilling Co.

Well Description: NE NW NE
Sec. 5-13S-16W
Ellis County, Kansas



Elevation: 2,004' KB

Treatment:

Production: D & A

Tops:

CASING RECORD

| Size | Run | Pulled |
|--------|------|-----------------|
| 8 5/8" | 210' | Cmtd. w/135 sax |

..... Figures Indicate Bottom of Formations

| | |
|--------------|------------|
| Shale | 213' |
| Shale & sand | 1,075' |
| Shale | 1,154' |
| Anhydrite | 1,190' |
| Shale | 2,225' |
| Shale & lime | 2,385' |
| Shale | 2,533' |
| Shale & lime | 3,235' |
| Lime | 3,505' RTD |

RECEIVED
STATE CORPORATION COMMISSION

NOV 28 1995

COMMISSION
WICHITA KANSAS