

KANSAS  
STATE CORPORATION COMMISSION

*OK*

WELL PLUGGING SUPERVISOR'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 93-5 Location: NE NE NW  
County: Ellis Sec. 13 Twp. 11 Rge. 17 (E) (W)  
Name of Field or Pool: \_\_\_\_\_ Total Depth: 3475

I have this date completed supervision of plugging of:

Well No. 1 Lease Cress

Operator's Full Name Smitherman & Leeder Leeper ANBYCC

Complete Address: 3130 Cherry Ridge Road Engelwood, Colo.

Plugging Contractor: West Supply Co

Address: Chase, Kans License No. 14

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

If well is a rotary drilled dry hole did operators wait for you to arrive \_\_\_\_\_

If yes how long \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 10AM Day 22 Month 4 Year 58

The above well was plugged as follows:

8 5/8" at 656' circulated with cement - 5 1/2" 3475 cemented - perf 3339'  
Filled with sand to 3320', set 4 sax cement with dump bailer, pulled  
3000' 5 1/2" to 550', circulated hole with heavy mud through 5 1/2" (60 sax  
Gel), displaced 20 sax cement through 5 1/2" at 550', heavy mud to 240',  
displaced 20 sax cement through 5 1/2" at 240', heavy mud to 35', set  
rock and 10 sax cement to 0'.

Mudding and cementing by West Supply Co pump truck.

I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed: *[Signature]*  
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Reviewed: *[Signature]*  
Field Supervisor

Signed: \_\_\_\_\_  
Well Plugging Supervisor

Remarks:

APR 25 1958  
04-25-58  
CORPORATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 13 T. 11 R. 174  
BOCK PAGE 93 LINE 5