

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

15-051-02186-0000

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

STATE CORPORATION COMMISSION  
AUG 31 1961  
08-31-61  
CONSERVATION DIVISION  
Wichita, Kansas

File No. \_\_\_\_\_ County: Ellis  
Location: CS $\frac{1}{2}$  SW NW Sec. 17 Twp. 11 Rge. \_\_\_\_\_ (E) \_\_\_\_\_ (W) 17  
Name of Field: \_\_\_\_\_ Total Depth: 3375

I have this date completed supervision of plugging of:

Lease Name: Carmichael Well No. C-1

Operator's Full Name: Pan American Oil Pet Corp

Complete Address: Box 1654 Oklahoma City, Okla

Plugging Contractor: Knight Casing Pulling Co

Address: Chase, Kansas License No. 436

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 6:30PM Day 25 Month 8 Year 61

The above well was plugged as follows:

15" 60' - 10" 1124' circulated with cement - 7" 3375' 150 sax cement  
178' 2" tubing lost in hole.

Set plug at 3280', sand to 3230', set 5 sax cement with dump bailer,  
pulled 2500' 7" to 500', circulated hole with heavy mud through 7"  
18 sax Gel), displaced 25 sax cement through 7" at 450', heavy mud to  
170', displaced 25 sax cement through 7" at 170', heavy mud to 30', set  
bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Knight Casing Pulling pump truck.

Signed: [Signature]  
Conservation Division Agent

Reviewed: [Signature]  
Field Supervisor

Remarks:

INVOICED  
DATE 9/8/61  
INV. NO. 3403-W