

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 30 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Clinton Oil Company

Complete Address P. O. Box 1201 Wichita, Kansas 67201

Lease Name J. Carmichael "C" Well No. 4

Location C - N/2 SE NW ~~SZ UUUU~~ ^{AMB KCC} Sec. 17 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3361'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Pipe Pulling

Address Box 176 Chase, Kansas 67524 License No. 683

Operation Completed: Hour 2:30 P Day 28 Month 8 Year 1974

The above well was plugged as follows:

- TDC. 3361' 8 10 3/4 csg set at 1096' cwc 600 sx. 15" csg 35' cwc
- 7" csg set at 3352' cw 200 sx cem.
- Set 7" wood plug 3304' -dumped 5 sk cem W/dump bailer. (3304-3250)
- Cutoff & recovered 2202' of 7" csg.
- Filled 10 3/4 csg with mud to 365' -set rock & sand bridge (365-350)
- Filled with RMC from 350' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Marney
Well Plugging Supervisor

DATE 8/30/74
INV. NO. 9801-U