

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 19 1975
09-19-75
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Champlin Petroleum Company
Complete Address 6051 N. Brookline, Suite 116, Oklahoma City, Oklahoma 73112
Lease Name Hadley "D" Well No. 6
Location C S/2 NE SW Sec. 17 Twp. 11 Rge. (E) (W) 17
County Ellis Total Depth 3441'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Knight Casing Pulling
Address Box 405 Chase, Kansas 67524 License No. 436
Operation Completed: Hour 11 A Day 18 Month 9 Year 1975

The above well was plugged as follows:

Total Depth 3441' 8 5/8 csg set 1152' cwc 600 sk.
4 1/2 csg set 3340' cw 150 sk cmt.
4 1/2 csg PBD 3350' & perf. (3028-2862)
Set 4 1/2 wood plug at 2800' -poured 10' sd -dumped 3 sk cmt W/dump bailer. (2800-2760)
Cutoff & recovered 2205' of 4 1/2 csg.
Set 8 5/8 wood plug at 400' -10' rock & sand bridge & RMC to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 9-23-75

INV. NO. 1940-W