

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
APR 27 1972  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Champlin Petroleum Company

Complete Address Box 308 Ellinwood, Kansas 67526

Lease Name Hadley "D" Well No. 7

Location C N/2 NE SW Sec. 17 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3429'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Co. Tools by HOWCO

Address        License No.       

Operation Completed: Hour 12:30 P Day 25 Month 4 Year 1972

The above well was plugged as follows:

Total Depth 3429' 8 5/8 csg set at 1150' cwc Cmt. Mat. "Halco-Light"

4 1/2 csg set at 3429' cw 175 sk cmt.

4 1/2 csg perf. (3392-3401 1/2) Dak. Sq. No pipe recovered.

Ran 51 jts <sup>159</sup> set at 1560' -pumped 22 sk gel W/100 lbs hulls, -displaced 20 sk cmt.

Pulled 37 jts tbg set at 420' -pumped 65 sk gel & water -displaced 40 sk cmt. (4-20-72)

Ran wire line to top of fluid (268') pumped down 4 1/2 csg with 60 sk cmt. (4-21-72)

Ran wire line -top of cement 113' -Filled to surface with 20 sk cmt. (4-25-72)

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 5-3-72

INV. NO. 5648-W