

R

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 051 - 02202 - 0000 (of this well)

Operator's Full Name CHAMPLIN PETROLEUM COMPANY'S.
Complete Address 2601 NORTHWEST EXPRESSWAY SUITE 800E OKLA. CITY, OKLA.
Lease Name HADLEY Well No. # 10 - "D" 73112
Location C - 5/2 NW-SW Sec. 17 Twp. 11 Rge. 17 (E) (W) W
County ELLIS Total Depth 3436 FT.
Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor CHAMPLIN PETROLEUM COMPANY

Address 2601 NORTHWEST EXPRESSWAY SUITE 800E OKLA. CITY, OKLA. License No. _____

Operation Completed: Hour 1:15 PM Day 5th Month JULY Year 1979

The above well was plugged as follows:

8 5/8" 1128^{EE} S.P. CMC? - 4 1/2" - 3436^{EE} CMC?
PERF - 3385^{EE} TO 3392^{EE} - PIPE COLLAPSED AT 2200^{EE}.
ORDERED 60ST 50ST Pozmix 6% GEL - 50ST COMMON 10% SALT.
2ST HULL'S & 8ST GEL. - (PUMPED WITH PUMP TRUCK)
LOWERED 2 1/2" TUBING TO 2200^{EE} PUT IN 50ST COMMON 10% SALT.
REMOVED TUBING AND PUT IN 8 5/8" S.P. - 1ST HULL'S - 8ST GEL.
1ST HULL'S RELEASED PLUG AND 40ST CMT. - ALSO
PUT 20ST 50ST Pozmix 6% GEL IN ANNULUS. - CEMENTED BY HALLIBURTON

I hereby certify that the above well was plugged as herein stated.

ON 10th OF JULY.
RETURNED AND PUT
1/2 YD. Ready Mix
AND FILLED TO TOP.

STATE CORPORATION COMMISSION

JUL 12 1979

CONSERVATION DIVISION
Wichita, Kansas

Signed: Marvin Schmidt
Well Plugging Supervisor

INVOICED

DATE 7-12-79

INV. NO. 0008-W