

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NE SW SW

SEC. 17 TWP. 11 RGE. 17

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. D-11 Lease _____ Hadley _____

Operator Champlin Refg Co Address Ellinwood, Kans

Field Bemis County Ellis

Total Depth 3480 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 1200' circulated with cement - 4 1/2" at 3466' with
200 sax cement behind - Pipe parted and mudded self to
1545', set 5 sax cement at 1545', shot and pulled 1500' 4 1/2",
filled hole with mud to 250', set rock and 20 sax cement,
filled with mud to 35', set rock and 10 sax cement to bottom
cellar.

RECEIVED
STATE CORPORATION

AUG 6 X 1951

CONSERVATION DIVISION
Wichita, Kansas

[Signature]
District Conservation Agent

Date 8-1-51

PLUGGING
FILE SEC 17 TWP. 11 R. 17
BOOK PAGE 100 LINE 29