

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 5 1972  
09-05-72  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Champlin Petroleum Company

Complete Address Box 308 Ellinwood, Kansas 67526

Lease Name Hadley "D" (SWD) Well No. 14

Location S/2 SE SE Sec. 17 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3882'

Abandoned Oil Well        Gas Well        Input Well        SWD Well XX D & A       

Other well as hereafter indicated       

Plugging Contractor Co. Tools by HOWCO

Address        License No.       

Operation Completed: Hour 10:15 A Day 28 Month 8 Year 1972

The above well was plugged as follows:

Total Depth 3882' 10 3/4 csg set at 1160' cwc 500 sk. Cmt. Mat. "Halib-Light"

7" csg set at 3825' cw 200 sk cmt.

7" csg perf. (3565-3820)

2" tubing & packer stuck in hole. No pipe recovered.

Pumped down 2" tbg & circulated 7" anulus with 100 sk cmt. Closed 7" anulus and

squeezed 2" tbg with 30 sk cmt W/100 lbs hulls.

Pumped down 10 3/4 anulus with 50 sk cmt W/500 lbs pres.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo. F. Wessley  
Well Plugging Supervisor

INVOICED

DATE 9/5/72

INV. NO. 6266-u