

KANSAS

AL STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 27 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Champlin Petroleum Company

Complete Address Box 308 Ellinwood, Kansas 67526

Lease Name Hadley "D" Well No. 16

Location SW SW SW Sec. 17 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3609'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Co. Tools by HOWCO

Address License No.

Operation Completed: Hour 4:15 P Day 21 Month 4 Year 1972

The above well was plugged as follows:

Total Depth 3609' 8 5/8 csg set at 215' cwc 150 sk. Cmt. Mat. "Halco-Light"

5 1/2 csg set at 3608' cw 150 sk cmt.

5 1/2 csg PBTB 3600' with perf. (3534-3598)

5 1/2 csg 2-stage collar set at 1287' circ with Black-Magic. No pipe recovered.

Ran 104 jts tbg set at 3175' -pumped 25 sk gel & water W/100 lbs hulls, -displaced

25 sk cmt. Pulled tbg and ran wire line to 550' -set rock & sand bridge (535-550)

Filled with 60 sk cmt from (535 to base of cellar)

Pumped 20 sk cmt down annulus with 100 lbs pres.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Marney
Well Plugging Supervisor

INVOICED

DATE 5-3-72

INV. NO. 5646-42