

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION

APR 21 1972

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Champlin Petroleum Company

Complete Address Box 308 Ellinwood, Kansas 67526

Lease Name Mock Well No. 1

Location SW SW NE Sec. 17 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3383'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Co. Tools by HOWCO

Address _____ License No. _____

Operation Completed: Hour 12:30 P Day 19 Month 4 Year 1972

The above well was plugged as follows:

Total Depth 3383' 16" csg set at 71' cwc 100 sk 10 3/4 csg set at 1060' cwc 600 sk.

7" csg set at 3351' cw 200 sk. 5 1/2" liner (3316-3383) cemented.

7" csg squeezed at 205' circ to surface with 200 sk cmt.

Ran 104 jts tbg set at 3175' -pumped 45 sk gel & water W/100 lbs hulls -displaced

35 sk cmt. Pulled 92 jts tbg set at 360' -circulated 55 sk cmt to surface. Pulled

remaining 12 jts tbg -capped 7" csg W/5 sk cmt. Annulus circ to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 4/21/72

INV. NO. 5600-W