

15-051-02204-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 19 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name ChAMPLIN Petroleum Company

Complete Address Box 308 Ellinwood, Kansas 67526

Lease Name Mock Well No. 2

Location NE SW NE Sec. 17 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3359'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Co. Tools by HOWCO

Address License No.

Operation Completed: Hour 1:30 P Day 17 Month 4 Year 1972

The above well was plugged as follows:

Total Depth 3359' 8 5/8 csg set at 1006' cwc 750 sk. Cmt. Mat. "Halco-Light"

4 1/2 csg set at 3347' cw 200 sk cmt.

4 1/2 csg squeezed at 558' W/170 sk cmt. No pipe recovered.

Ran 104 jts tbg set at 3175' -pumped 20 sk gel & water W/100 lbs hulls -displaced

20 sk cmt. Pumped 92 jts tbg set at 360' -circ. 30 sk cmt to surface. Pulled

remaining 12 jts tbg -capped 4 1/2 csg W/5 sk cmt.

Pressured-up on annulus 1200 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 4-19-72

INV. NO. 5590-W