

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 19 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Champlin Petroleum Company

Complete Address Box 308 Ellinwood, Kansas 67526

Lease Name Mock Well No. 3

Location SW NW NE Sec. 17 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3358'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Co. Tools by HOWCO

Address License No.

Operation Completed: Hour 11:30 A Day 18 Month 4 Year 1972

The above well was plugged as follows:

Total Depth 3358' 8 5/8 csg set at 1058' cwc 240 sk. Cmt. Mat. "HalcopLight"

4 1/2 csg set at 3359' cw 175 sk cmt.

No pipe recovered.

Ran 104 jts tgb set at 3175' -pumped 20 sk gel & water W/100 lbs hulls -displaced'

20 sk cmt. Pulled 92 jts tbg set at 360' -circ. 30 sk cmt to surface. Pulled

remaining 12 jts tbg & capped 4 1/2 csg W/5 sk cmt.

Pumped 50 sk cmt down anulus with 300 lbs pres.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 4-19-72

INV. NO. 5591-W