



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

AUG 26 1974
08-26-74
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Clinton Oil Company

Complete Address Box 1201, Wichita, Kansas 67201

Lease Name J. Husted Well No. 1

Location C N/2 NW ~~NW~~ SW ^{AVE} Sec. 18 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3336'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelse Pipe Pulling

Address Box 176, Chase, Kansas License No. 683

Operation Completed: Hour 11:15 P Day 21 Month 8 Year 1974

The above well was plugged as follows:

Total Depth 3336' 15" csg 55' cwc 10 3/4 csg 1092' cwc

7" csg set at 3333' cw 250 sk.

7" csg PBD 3410' with top perf. (3396)

5" liner (3259-3437)

Set 7" wood plug at 3259' -dumped 5 sk cem W/dump bailer.

Cutoff and recovered 2419' of 7" csg.

Filled 10 3/4 csg W/mud to 400' -set rock & sand bridge (400-350)

Filled with readymix cement from 350' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Mursay
Well Plugging Supervisor

INVOICED

DATE 8/27/74

INV. NO. 9765-W