

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3
Rev. 6-4-68

RECEIVED
STATE CORPORATION COMMISSION

JUL 21 1980

CONSERVATION DIVISION
Wichita, Kansas
(of this well)

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - ✓

Operator's Full Name ENERGY RESERVES GROUP, INC.
Complete Address 925 PATTON ROAD, - GREAT BEND, KANS. 67530
Lease Name J. HUSTED Well No. IF 3
Location Q-5 1/2 - NE - SW Sec. 18 Twp. 11 Rge. 17 (E) (W) W
County ELLIS Total Depth 3359 FE
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor HALLIBURTON CEMENTING

Address EAST HWY. 40 - HAYS, KANS. 67601 License No. _____

Operation Completed: Hour 11:40 AM Day 18th Month JULY Year 1980

The above well was plugged as follows:

15 1/2" 40 FE w/80^{SE} CMT. → 10 3/4" 1120 FE w/500^{SE} CMT.
7" - 22^{LB} SET AT 3455' FE w/200^{SE} CMT. → 5" LINER 3165' - 3435'
5 1/2" LINER 2947' - 3161' FE.

PROPOSED DISPOSAL - GOT TO 3407' FE HIT IRON AND ABANDONED
PERFS AT 3403-3404 - OLD PERFS 3414-3415 [NO PIPE RECOVERY]

ORDERED 250^{SE} HALLIBURTON LIGHT - 22^{SE} GEL.
IN 7" PUT IN 35^{SE} CMT. - 22^{SE} GEL. AND 155^{SE} CMT. MAX PRESSURE 250^{LB}

IN ANNULUS 7 1/2 + 10 3/4 → 60^{SE} CMT. MAX PRESSURE 300^{LB} - ANNULUS IN
15 1/2 AND 10 3/4 - CEMENTED TOP TO BOTTOM.

I hereby certify that the above well was plugged as herein stated (BY HALLIBURTON CMT)

INVOICED

DATE 7-22-80

INV. NO. 2634-W

Signed: Marion Schmidt
Well Plugging Supervisor

15-051-02215-0002

THE DICKEY OIL COMPANY

Husted #3 Well

LOCATION: C/S $\frac{1}{2}$ NE $\frac{1}{4}$ SW $\frac{1}{2}$ 18-11-17
Ellis County, Kansas

ELEVATION:

COMMENCED: 7/7/40
COMPLETED: 7/29/40

15 $\frac{1}{2}$ " 40'
10" 1120'
7" 3355'

shale and sand	37
post rock	40
shale and shells	490
iron	525
sand	560
shale and shells	630
sand	750
red bed	1105
anhydrite	1140
shale and shells	1470
salt	1650
shale and shells	1782
broken lime	1910
shale and lime	1977
broken lime	2351
shale	2400
shale and shells	2680
broken lime	2775
shale and shells	2798
top Topeka	2798
lime	3095
shale and shells	3118
top K. C. lime	3118
lime	3312
red bed	3324
conglomerate	3345
green shale	3355
top Arbuckle	3355
lime	3359 T.D.

RECORDED
INDEXED
JUN 23 1940
06-23-80