

KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number ~~15-707~~ 051-02216-0000

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Energy Reserves Group, Inc.

Complete Address 925 Patton Road, Great Bend, Ks. 67530

Lease Name J Husted Well No. 4

Location S/2 NW SW Sec. 18 Twp. 11 Rge. 17 (East) (West)

County Ellis Total Depth 3342'

Abandoned Oil Well XXXX Gas Well      Input Well      SWD Well      D&A     

Other well as hereinafter indicated     

Plugging Contractor Halliburton Services

Address 1100 E. 8th. St., Hays, Ks. 67601 License No.     

Operation Completed: Hour: 5:45 PM Day: 12 Month: May Year: 19 82

Plugging Operations attended by Agent?: All XXXX Part      None     

The above well was plugged as follows:

10"-1109' S.P. cuc w/common. 7" casing set at 3335' w/common. 7' of open hole.  
Ordered 140 sacks 50/50 posmix-4% Gel.-3% Cal.Cl., 19 sacks Gel., 5 sacks hulls  
& 7" plug. Pumped into 7" casing w/ pump truck 4 sacks hulls, 15 sacks Gel., 70  
sacks cement, 4 sacks Gel., 1sack hulls, released plug & followed w/70 sacks  
cement. Pumped into 10" S.P. 560 pounds pressure. Maximum pressure 550 pounds.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 18 1982 RMD

05-18-82

CONSERVATION DIVISION  
Wichita, Kansas

Amount of Surface Casing: 1109' of 10" S.P.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed:       
Conservation Division Agent

INVOICED  
DATE 5-19-82  
INV. NO. 186-W  
187