



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

AUG 19 1974

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Clinton Oil Company  
Complete Address Box 1201, Wichita, Kansas  
Lease Name J. Husted Well No. 5  
Location C N/2 SW SW Sec. 18 Twp. 11 Rge. (E) (W) 17  
County Ellis Total Depth 3343'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Kelse Pipe Pulling  
Address Box 176, Chase, Kansas 67524 License No. 683  
Operation Completed: Hour 4 P Day 16 Month 8 Year 1974

The above well was plugged as follows:

- Total Depth 3343' 20 3/4 csg set at 1100' cwc.
- 7" csg set at 3332' cemented.
- Filled 7" csg W/sd (3343'-3300') dumped 5 sk cmt W/dump bailer. (3300-3275)
- Cutoff and recovered 2318' of 7" csg.
- Filled 10 3/4 csg W/mud to 365' -set rock & sand bridge (365-350)
- Filled with readymix cement from 350' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/19/74  
INV. NO. 9717-W

Signed: L. J. Massey  
Well Plugging Supervisor