

KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number ~~15-240~~ 15-051-19329-0001

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Energy Reserves Group, Inc.

Complete Address 925 Patton Road, Great Bend, Ks. 67530

Lease Name Noni Kollman Well No. 2

Location S/2 SW NE Sec. 18 Twp. 11 Rge. 17 (East) (~~West~~)

County Ellis Total Depth 3477'

Abandoned Oil Well XXX Gas Well      Input Well      SWD Well      D&A     

Other well as hereinafter indicated     

Plugging Contractor Halliburton Services

Address 1100 E. 8th. St., Hays, Ks. 67601 License No.     

Operation Completed: Hour: 2:30 PM Day: 12 Month: May Year: 19 82

Plugging Operations attended by Agent?: All XXXX Part      None     

The above well was plugged as follows:

10 3/4"-1116' S.P. cuc. w/475 sacks common. 7" set 3360' w/175 sacks common.  
Top perf. 3418'. Ordered 140 sacks 50/50 posmix-4% Gel.-3% Cal.Cl., 19 sacks  
Gel., 5 sacks hulls & 7" plug. Pumped into 7" casing w/pump truck, 4 sacks hulls,  
15 sacks Gel., 70 sacks cement, 4 sacks Gel., 1 sack hulls, released plug &  
followed w/70 sacks cement. Checked 10 3/4" S.P. Maximum pressure 400 pounds.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 18 1982

Amount of Surface Casing: 1116' of 10 3/4"

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

~~\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_~~

Signed: \_\_\_\_\_  
Conservation Division Agent

INVOICED

DATE 5-19-82

INV. NO. 126-W