

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 18 1961  
CONSERVATION DIVISION  
Wichita, Kansas

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Ellis  
Location: CW $\frac{1}{2}$  SE NE Sec. 18 Twp. 11 Rge. 17 (E) (W) \_\_\_\_\_  
Name of Field: \_\_\_\_\_ Total Depth: 3351

I have this date completed supervision of plugging of:

Lease Name: Hollman Noni Hollman AUBKCC Well No. 5  
Operator's Full Name: Pan American Pet Corp  
Complete Address: Box 548. Ellinwood, Kansas  
Plugging Contractor: Knight Casing Pulling Co  
Address: Chase, Kansas License No. 436  
Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_  
Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No   
If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 1PM Day 11 Month 4 Year 61

The above well was plugged as follows:  
10 3/4" 1100' circulated with cement - 7" 3372' with 200 sax cement.  
Hole in 7" - hole sanded up to 2500' - pulled 2450' 7" casing.  
Filled hole with heavy mud to 350' ( 20 sax Gel), set 20 sax cement at  
350', heavy mud to 150', set 20 sax cement at 150', heavy mud to 25',  
set bridge and 10 sax cement to bottom cellar.  
Mudding and cementing by Knight Casing Pulling pump truck.

Signed: [Signature]  
Conservation Division Agent

Reviewed: [Signature]  
Field Supervisor

Remarks:

INVOICED  
DATE 4/28/61  
INV. NO. 3002-W