



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 15 1974  
08-15-74  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Clinton Oil Company

Complete Address Box 1201, Wichita, Kansas 67201

Lease Name J. Husted Well No. 6

Location C S/2 SW SW Sec. 18 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3485'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Pipe Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 4 P Day 13 Month 8 Year 1974

The above well was plugged as follows:

Total depth 3485' 10 3/4 csg set at 1135' cwc 475 sk/

7" csg set at 3357' cw 175 sk cmt.

5" liner cemented & perf. (3357-3415)

Set 7" wood plug at 3357' & dumped 5 sk cmt W/dump bailer.

Cutoff & recovered 2318' of 7" csg.

Filled 10 3/4 csg with mud to 365' -set rock & sand bridge (365-350)

Filled with readymix cement from 350' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/19/74

INV. NO. 9718-W

Signed: Leo F. Massey  
Well Plugging Supervisor