

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Wichita State Office Building  
130 South Market, Room 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-177

API NUMBER 15-051-249250000

LEASE NAME Brungardt F

WELL NUMBER 1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

990 Ft. from S Section Line

990 Ft. from E Section Line

LEASE OPERATOR R.P. Nixon Operations, Inc.

SEC. 19 TWP. 13S RGE. 16W (E) or (W)

ADDRESS 207 West 12th Street Hays, KS 67601

COUNTY Ellis

PHONE #(913) 628-3834 OPERATORS LICENSE NO. 5252

Date Well Completed 6/14/96

Character of Well D & A

Plugging Commenced 6/17/96

(Oil, Gas, D&A, SWD. Input, Water Supply Well)

Plugging Completed 6/17/96

The plugging proposal was approved on 6/17/96 (date)

by Marion Schmidt (KCC District Agent's Name).

Is ACO-1 Filed? not yet - newly If not, is well log attached? yes  
drilled well

Producing Formation dry hole Depth to Top Arbuckle perms Bottom T.D. 3553'  
from 3499'-3502'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS RECEIVED		CASING RECORD				
Formation	Content	From	To	Size	Put in	Pulled out
	<u>07-18-1996</u> <u>JUL 18 1996</u>			8 1/2"	206'	None
				5 1/2"	3551'	2500'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from     feet to     feet each set.

Sanded back to 3440' and dumped 5 sx Portland cement on top of sand. Shot casing off @ 2500'. Pulled to 1700' and pumped 105 sx 60/40 Poz, 10% gel w/200# hulls. Pulled to 1140' and pumped 30 sx same cement w/100# hulls. Pulled to 540' and pumped 30 sx same cement w/100# hulls. Pulled to 175' and circulated 30 sx same cement w/100# hulls.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Jay-Lan Corporation License No. 5128

Address 207 West 12th Street Hays, KS 67601-3898

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R.P. Nixon Operations, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Dan A. Nixon (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *Dan A. Nixon*

(Address) 207 West 12th St. Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 17th day of July, 19 96



Roxie VonIntel  
Notary Public

My Commission Expires: 5-24-97

15-051-24925-00-00

**ELI** **ELI** **WIRELINE** **RADIATION**  
**SERVICES** **GUARD**  
**LOG**  
 15-051-24925

COMPANY R.P. NIXON OPER., INC. WELL BRUNGARDT F #1 FIELD COUNTY ELLIS STATE KS	COMPANY R.P. NIXON OPER., INC. WELL BRUNGARDT F #1 FIELD COUNTY ELLIS STATE KS	
	LOCATION SEC. 19 TWP. 13S RGE. 16W	OTHER SERVICES:

PERMANENT DATUM GROUND LEVEL ELEV. 1978 ELEV. K.B. 1983  
 LOG MEASURED FROM K.B. 85 FT. ABOVE PERMANENT DATUM D.F.  
 DRILLING MEASURED FROM KELLY BUSHING G.L. 1978

DATE	5 28 96			
RUN NO.	001			
DEPTH-DRILLER	3553			
DEPTH LOGGER	3551			
B.M. LOG INTER.	3550			
TOP LOG INTER.	2850			
CASING-DRILLER	206			
CASING LOGGER				
BIT SIZE	7 7/8			
FLUID TYPE	CHEMICAL MUD			
DENS. : VISC.	9.4/47			
PH : FLUID LOSS	10.5/10.8			
SOURCE OF SAMPLE	FLOW LINE			
RMI @ MEAS. TEMP.	1.0 @ 201			
RMI @ MEAS. TEMP.	0.75 @ 201			
RMC @ MEAS. TEMP.	1.20 @ 201			
SOURCE : RMI/RMC	CALC/CALC			
RM @ BHT	0.56 @ 106			
TIME SINCE CIRC.	2 HOURS			
MAX. REC. TEMP.	106 F			
EQUIP. : LOCATION	147/HAYS			
RECORDED BY	GLENN NEWELL			
WITNESSED BY	DAN NIXON			