


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County. Sec. 19 Twp. 13 Rge. 16 (E) W (W)
Location as "NE/CNW*SW*" or footage from lines. C S/2 SE NW
Lease Owner K & E Drilling, Inc.
Lease Name Geist Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19____
Application for plugging filed 19____
Application for plugging approved 19____
Plugging commenced 7-13-60 19____
Plugging completed 7-15-60 19____
Reason for abandonment of well or producing formation ~~XXXXXXXX~~ Depleted.

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3529 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	248'	None
				5-1/2"	3518'	3017'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3529', sanded to 3500'

and dumped 4 sacks of cement @ 3500'
with dump bailer. Pulled 55 jts. of
5 1/2" casing and circulated with 15 sacks
of mud and 20 sacks of cement. Pulled
16 jts. of 5 1/2" casing and circulated
with 20 sacks of cement. Pulled balance
of 5 1/2" casing, bailed hole to 30' and
ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of September, 1962

Milton J. Volin
Notary Public.

My commission expires May 20, 1964



RECEIVED
STATE CORPORATION COMMISSION
SEP 27 1962
09-27-1962
CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S WELL LOG

OPERATOR: K & E DRILLING, INC., ET AL
719 Union Center Building
Wichita, Kansas

WELL NAME: #1 GEIST
LOCATION: CS/2 SE NW
Sec. 19-13S-16W
ELLIS COUNTY, KANSAS

CONTRACTOR: K & E DRILLING, INC.
719 UNION CENTER BLDG.
WICHITA, KANSAS

COMMENCED: 10-8-59
COMPLETED: 10-17-59
ELEVATION: 1996' KB, 1993' DF
PRODUCTION: ARBUCKLE - OIL

CASING RECORD: 8-5/8" @ 248 (165 sx cmt)
5-1/2" @ 3518' (75 sx cmt)

ROTARY TOTAL DEPTH: 3522'

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Surface Soil (Cellar)	8
Clay	65
Blue Shale	248
Shale	400
Sand	465
Shale	525
Red Bed	1145
Anhydrite	1180
Shale & Shells	2085
Lime & Shale	2675
Lime	2880
Lime & Shale	3030
Lime	3165
Lime & Shale	3240
Lime	3522
R.T.D.	3522

RECEIVED
STATE CORPORATION COMMISSION
SEP 26 1962
09-26-1962
CONSERVATION DIVISION
Wichita, Kansas

CERTIFICATION

State of KANSAS
County of SEDGWICK ss.

I, Dale Silcott of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

Dale Silcott
Dale Silcott

Subscribed and sworn to before me this 21st day of October, 1959.

Patricia M. Edwards
Patricia M. Edwards Notary Public

My Commission expires: August 11th, 1962.

