


15-051-04609-00-00

WELL PLUGGING RECORD

Information Completely  
Required Affidavit  
Deliver Report to:  
Conservation Division  
State Corporation Commission  
221 No. Broadway  
Wichita, Kansas

Ellis County, Sec. 19 Twp. 13 Rge. 16 (E) (W)  
Location as "NE/CNW/SW" or footage from lines SW NE SW

Lease Owner Jay Kornfeld  
Lease Name Geist Well No. 1  
Office Address 623 Union National Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5-6-64 19  
Application for plugging filed 5-6-64 19  
Application for plugging approved 5-6-64 19  
Plugging commenced 5-6-64 19  
Plugging completed 5-6-64 19  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 3538 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FRDM	TD	SIZE	PUT IN	PULLED OUT
				8 5/8"	201'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st Plug @ 540' with 20 sacks cement  
2nd Plug @ 180' with 20 sacks cement  
3rd Plug @ 35' 1/2 sack hulls and 10 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION

MAY 12 1964

05-12-1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.  
Address P. O. Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

P. O. Box 486, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 8th day of May, 19 64

My commission expires April 1, 1967

Ulanda Nichols

Notary Public.

DRILLER'S LOG

COMPANY: Jay Kornfeld  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: GEIST #1  
 LOCATION: SW NE SW Sec. 19-13-16  
 ELLIS COUNTY, KANSAS  
 COMMENCED: 4-29-64  
 COMPLETED: 5-6-64

-----		
0	70	Surface Soil & Clay
70	100	Sand & Shale
100	201	Shale
201	320	Shale & Shells
320	500	Shale & Redbed
500	740	Sand & Shale
740	1123	Redbed & Shale
1123	1166	Anhydrite
1166	1570	Shale & Shells
1570	1925	Shale & Shells with Lime Streaks
1925	3075	Lime & Shale
3075	3475	Lime
3475	3508	Lime & Shale
3508	3538	Conglomerate
	<u>3538</u>	<u>Rotary Total Depth - d. &amp; a.</u>

-----  
 Set 8 5/8" used casing @ 201' with 150 sacks Sunset  
 -----

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Geist #1 well, located SW NE SW of Section 19, Township 13, Range 16, Ellis County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite  
 Leslie Kite

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 8th day of May, 1964.



Ulanda Nichols  
 Ulanda Nichols

My Commission Expires  
 April 1, 1967

RECEIVED  
 STATE CORPORATION COMMISSION

MAY 12 1964  
 05-12-1964  
 CONSERVATION DIVISION  
 Wichita, Kansas