

WELL PLUGGING RECORD

OR FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

STATE OF KANSAS STATE CORPORATION COMMISSION Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 800 Biting Building Wichita, Kansas

Ellis County. Sec. 20 Twp. 13 Rge. 11/E/16 (W) Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. C. N/2 NW Lease Owner. Crow Drilling Co. Lease Name. Lang Well No. 1 Office Address. Shreveport, Louisiana Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole Date well completed. 10-13-41 Application for plugging filed. 11-3-41 Application for plugging approved. 11-3-41 Plugging commenced. 11-1-41 Plugging completed. 11-1-41 Reason for abandonment of well or producing formation Dry Hole If a producing well is abandoned, date of last production Dry Hole Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Section Plat grid with 'NORTH' label above it.

Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well. C. T. Alexander Producing formation. Depth to top. Bottom. Total Depth of Well. 3585 Feet Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with columns: Formation, Content, From, To, Size, Put In, Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with mud from 3585' to 400' and hole bridged at 400' and cement to 380' and mud to 38' and cement to 8'.

Handwritten stamp: FEB 2 1948 02-247948

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. Crow Drilling Co. Address. 422 Commercial Nat'l Bank Bldg. Shreveport, Louisiana,

STATE OF _____, COUNTY OF _____, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) David Crow (Address)

SUBSCRIBED AND SWORN to before me this 20th day of February 1948 A. G. Robertson Notary Public.

My commission expires

with life in Ia.

PLUGGING FILE SEC 20 T 13 R 16 BOOK PAGE 13 LINE 6

7-47-10M

1
 C $\frac{1}{2}$ NE NW Lang
 20 13 16
 Crow Drig. Ellis
 10-13-41 Elev. 1973
 10-31-41

10 3/4 131 New casing Cem. with 65 sax Ash Grove cement by Halliburton

		<u>Geological Data</u>	
Shale & shells	0-140		
" "	288		
Sand	364	Anhydrite	1099
Sand & shale	390	Ft. Riley	2050
Red Shale	404	Florence	2150
Sand	490	Wreford	2220
Shale	520	Cottonwood	2350
Sand	540	Neva	2387
Shale & shells	636	Howard	2920
Sand	730	Topeka	2975
Red shale & shells	897	Heebner	3200
Shale	923	Lansing	3250
Red shale	1099	Base Kansas City	3483
Anhydrite	1144	Conglomerate	3499
Shale & shells	1504	Arbuckle	3568
Salt	1700	Total Depth	3585
Shale & lime	1795		
Broken Anhydrite	1929	No shows	
Lime	1980		
Shale & lime	2120		
Lime	2165	D & A	
Shale	2200		
Lime	2235		
Shale	2279		
Shale & lime	2507		
Lime	2554		
Shale & lime	2795		
Lime	2863		
Lime & shale	2910		
Shale	2928		
Lime	3232		
Shale & lime	3250		
Lime	3513		
Conglomerate	3570		
Dolomite	3585		

20 13 16W
 13 6