


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-051-00483-00-00
WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Ellis County. Sec. 33 Twp. 13S Rge. 16W (E) (W)
Location as "NE/CNW%SW%" or footage from lines SE/ SE/ NE/
Lease Owner Morgenstern & Specter
Lease Name Von Lintel Well No. I
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed Feb. 15, 1954 19
Application for plugging filed April 28, 1960 19
Application for plugging approved April 29, 1960 19
Plugging commenced 4/27/60 19
Plugging completed 5/2/60 19
Reason for abandonment of well or producing formation failure to produce profitably
If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty Hays, Kansas
Producing formation Conglomerate Depth to top 3454 Bottom 3465 Total Depth of Well 3465 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	340 ft.	none
				5 1/2" OD	3463	380 ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Circulated Mud at 375 feet. And Pumped 25 Sacks Cement at 375 feet.
Set a Ten foot Rock Bridge at 40 feet, Dumped Ten Sacks Cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 18 1960

CONSERVATION DIVISION
Wichita, Kansas

05-18-1960

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor E. & L. Casing Pulling Company NO. 377
Address Great Bend, Kansas

STATE OF Kanss, COUNTY OF Russell, ss.
Morgenstern & Specter, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So-help me God.

(Signature) Morgenstern

(Address) _____

SUBSCRIBED AND SWORN TO before me this 6th day of May, 1960

Elsie Leady
Notary Public.

My commission expires Dec 1, 1963



15-051-00483-00-00

COPY

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- ANCHUTZ DRILLING CO., INC.
Farm- Von Lintel No. 1

SEC. 33 T. 13 R. 16W
SE SW NE

Total Depth. 3468'
Comm. 2-5-54
Shot or Treated.
Contractor.
Issued. 4-3-54

Comp. 2-16-54

County Ellis
KANSAS



CASING:
8 5/8" 340' cem w/200 sx

Elevation. 1951

Production. 77 Bbls. Oil

Figures Indicate Bottom of Formations.

surface soil & sand	50
shale, sand & shells	345
shale & shells	390
sand	440
sand, stone & iron	445
iron pyrite & sand	475
Dakota sand	495
shale	505
red bed	1060
anhydrite	1095
shale, shells	1225
shale, shells & salt	1500
shale & shells	1790
lime & shale	1890
shale & lime	1995
lime & shale	2390
shale, lime & shells	2420
shale & lime	2655
lime & shale	2850
shale & lime	2980
lime & shale	2355
lime	3400
lime & shale	3465 RTD
lime & shale	3468
Total Depth.	

Tops: Scout	
Lansing	3200
Conglomerate	3454