

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-24,275-00-00

LEASE NAME Dortland

WELL NUMBER 1-23

SPOT LOCATION SE/4 SE/4 NW/4

SEC. 23 TWP. 13S RGE. 16W (E) or (W)

COUNTY Ellis

Date Well Completed 8/9/85

Plugging Commenced 8/9/85

Plugging Completed 8/9/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Graham-Michaelis Corporation

ADDRESS P. O. Box 247, Wichita, Kansas 67201

PHONE # (316) 264-8394 OPERATORS LICENSE NO. 5134

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #6, Hays, Kansas 67601-Gilbert Scheck

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3,465'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	338'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

1st Plug @ 3455' w/20 sx cement; 2nd Plug @ 1000' w/20 sx cement;
3rd Plug @ 550' w/100 sx cement; 4th Plug @ 400' w/40 sx cement;
5th Plug @ 40' w/10 sx cement & 1 sx Halls, 10 sx cement in rathole
(Plugs calculated by displacement) 200 sx 60/40 Pozmix, 6% Gel, 3% CC.

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company, Inc. License No. NA
Address Box 31, 332 W. Wichita, Russell, Kansas 67665


RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Sedgwick AUG 19 1985

Jack L. Yinger, Vice President (employee of operator) of above-described well, being first duly sworn on oath, I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack L. Yinger
(Address) P. O. Box 247, Wichita, KS 67201

SUBSCRIBED AND SWORN TO before me this 15th day of August, 1985

 **Aldine M. Johnson**
NOTARY PUBLIC
State of Kansas
MY APPT. EXPIRES 3-19-89

Aldine M. Johnson
Notary Public

My Commission expires: