


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Ellis County, Sec. 23 Twp. 13 Rge. 16 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW NW  
Lease Owner B & R Drilling, Inc.  
Lease Name Dortland Well No. # 1  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 12, 1950 19  
Application for plugging filed March 11, 1950 Verbally 19  
Application for plugging approved March 11, 1950 Verbally 19  
Plugging commenced March 12, 1950 19  
Plugging completed March 12, 1950 19  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough  
Producing formation Depth to top Bottom Total Depth of Well 3470' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	180'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugging Record

Filled hole with heavy mud to 180' Plug to 180'  
15 Sacks cement throu drill pipe. Heavey mud to  
35 ft plug @ 35 ft. 90 Sacks cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to B & R Drilling, Inc  
Address Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.  
Don Roberts (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Don Roberts*

Russell, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 14 th day of March, 19 50

*Clara Hummel*  
Notary Public.

My commission expires 6-17-50

PLUGGING  
FILE SEC 23 T 13 R 16 W  
BOOK PAGE 48 LINE 36

03-15-1950

B & R Drilling, Inc.  
Dortland #1

Sec. 23 Twp. 13 Rge. 16  
Ellis County, Kansas

Total Depth: 3470'  
Comm: 2/26/50  
Comp: 3/12/50

Casing

Cement

8 5/8" Set @ 180'

130 Sacks

Formation	Depth
Surface clay-Limestone	25
Shale-Shells-Sand	180
Shale-Shells	280
Sand-Shale	375
Sand	460
Shale-Pyrite	560
Sand	660
Shale-Pyrite	725
Shale-RedBed	1023
Anhydrite	1065
Shale	1195
Shale-Shells	1325
Shale-Salt	1450
Shale-Shells	1725
Anhydrite, Lime-Shale	1760
Lime-Shale	1895
Lime	2165
Lime-Shale	2843
Lime	3133
Shale	3153
Lime	3410
Conglomerate	3433
Lime	3436
Arbuckle Lime	3446
Lime	3470

STATE OF KANSAS )  
                          ) SS  
RUSSELL COUNTY )

I hereby certify that the above information is true and correct to the best of my knowledge.

Violet Feller

Subscribed and sworn to before me this 14th day of March, 1950

Clara Lummé

Notary Public

My commission expires: 6-17-50

PLUGGING  
PAGE 221 LINE 11  
PAGE 148 LINE 36

03-15-1950