

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-051-24,685 0000 (of this well).
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Diehl Oil, Inc. OPERATOR'S LICENSE NO. 09346

ADDRESS P. O. Box 234 Hays, KS 67601 PHONE # (913) 625-6711

LEASE (FARM) Peavey "D" WELL NO. 4 WELL LOCATION SW NW SW COUNTY Ellis

SEC. 19 TWP. 11 RGE. 17 ~~X~~ or (W) TOTAL DEPTH 3500 PLUG BACK TD 3473

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 279 CEMENTED WITH 150 SACKS

CASING SIZE 5 1/2" SET AT 3499 CEMENTED WITH 150 SACKS

PERFORATED AT 3488-90, 3483-85, 3466-72, 3442-48, 3434-38, 3426-38

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Sand to 50' above perforations. Set 5 sacks cement with bailer, shoot and pull 5 1/2" casing. Plug hole with 225 sacks 60/40 poz 8% gel with 5 sacks hulls.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? no
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Approx 12/19/90

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Glenn D. Diehl PHONE # (913) 625-6711

ADDRESS P. O. Box 234 Hays, KS 67601

PLUGGING CONTRACTOR Express Well Service LICENSE NO. 6426

ADDRESS Highway 40 Victoria, KS PHONE # (913) 735-9405

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Glenn D. Diehl
(Operator or Agent)

DATE: 12/14/90

(4)

1/81

1/81

STATE CORPORATION COMMISSION
DEC 16 1990
12-16-90

Mike Hayden
Governor

Keith R. Henley
Chairman

Rich Kowalewski
Commissioner

Jack Shriver
Commissioner

Judith McConnell
Executive Director

Frank A. Caro Jr.
General Counsel



Kansas Corporation Commission

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

December 18, 1990

Diehl Oil, Inc.
P.O. Box 234
Hays, KS 67601

Peavey "D" #4
SW NW SW 19-11-17W
Ellis County, KS
API No. 15-051-24,685

Gentlemen:


This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,


David P. Williams
Production Supervisor

District: #4, 2301 E. 13th
Hays, KS 67601
(913) 628 - 1200

Conservation Division
Shari Feist Albrecht
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238